

HOCHGERNER D-L 3560

Construction market components

Project Name

Hochgerner SEP 2003

Vienna down town

Presenter Name

Dusan Mojic

Project Goals

"Insurance building" in Vienna downtown

Indoor roof panels

Reclosable fastened

3M Dual-lock 3560

HPL panels to

Wooden construction



Description

Aircondition & electrical instalation

Covered by HPL reclosable panels



6 D-L strips on each panel 100mmX25mm + mechanical fixation 2 times per panel(with poles)

HPL panels prapplied with D-L in mnfg.



Primer 2262H used on HPL & wooden site

The secc.D-L strip applied ,pressure & primer on to the wooden construction





Req. For reclosable fastening system

3M Dual – Lock 3560 + primer 2262H

Primer on HPL and construction

Panels prepared with D-L in mnfg.

Wooden constr. Primed on site

900 panels to be installed

10 000€ total turnover ,SEP 2003







